

# **Ovation**<sup><sup>m</sup></sup> Series Automatic Transfer Switches

# **PRODUCT SPECIFICATIONS**

**DESCRIPTION**: A series of service entrance rated, open-transition automatic transfer switches integrated with a load center, offered in NEMA Type 1 or 3R enclosures, for use in residential and light commercial single phase standby power applications and compatible with stationary generators up to 50 kW. PowerPause<sup>TM</sup> Load Management Modules and surge suppression options are factory or field installable.

MODEL	POLES	CURRENT	VOLTAGE	PHASE	FREQUENCY	ENCLOSURE	ENCLOSURE SIZE	BRANCH	MOUNT	WEIGHT	LUG
		(Utility/Gen)	(nominal, AC)		(nominal, Hz)	RATING (NEMA)	(HxWxD inches)	CIRCUITS	Flush/Surface	(lbs)	CAPACITY
ATS1001D	2	100/100	120/240	1	60	Type 1	24 x 14.31 x 3.93	14	F/S	28	2/0 Al/Cu
ATS1001R	2	100/100	120/240	1	60	Type 3R	28 x 14.5 x 4.25	16	S	27	2/0 Al/Cu
ATS2001D	2	200/125	120/240	1	60	Type 1	42 x 14.31 x 3.93	38	F/S	46	300 Kcmil Al/Cu
ATS2001R	2	200/125	120/240	1	60	Type 3R	41 x 4.5 x 4.25	38	S	43	300 Kcmil Al/Cu
ATS2002R	2	200/200	120/240	1	60	Type 3R	23.5 x 18.5 x 4.25	4	S	23	300 Kcmil Al/Cu

# CONTROLLER

Voltage (nominal):	240 VAC (+/- 3%)					
Pickup	<204 or >270 VAC					
Dropout	<190 or >280 VAC					
Frequency (nominal):	60 Hz (+/- 2%)					
Pickup	<57 or >63 Hz					
Dropout	<54 or >66 Hz					
Time delays:						
Gen Start	5 seconds (utility voltage or frequency out of range)					
Load to Gen	10 seconds (verify voltage and frequency)					
Retransfer to Util	60 seconds (verify voltage and frequency)					
Gen Cooldown	300 seconds					
Generator Exerciser:						
Repeat interval	0, 7, 14, or 28 days					
Duration	15 minutes (10 min transferred, 5 min cool down)					
Load transfer	Optional					
Diagnostic Monitoring:						
Gen start/stop fail	ure (fast flash LED 4 – GENERATOR POWER)					
Gen over/under vo	Itage/frequency (slow flash LED 4 – GENERATOR POWER)					
Utility over/under	Utility over/under voltage/frequency (slow flash LED 2 – UTILITY POWER)					
Transfer failure to	Transfer failure to generator (slow flash LED 5 – GENERATOR LOAD)					
Transfer failure to utility (slow flash LED 1 – UTILITY LOAD)						
Motor drive fault (fast flash LED 3 – LOAD)						
Battery failure (fast flash LEDs 2+5 – UTILITY POWER + GENERATOR LOAD)						
Generator Signaling:						
Supports 2 or 4 wire (ON, +12V) or (CRANK, ON, +12V, -12V)						
PowerPause™ Load Management modules (optional, sold separately)						
Dynamic load management for up to six (6) 2 pole standby circuits						
PowerPause™ Relay Box (optional, sold separately)						

# **ENVIRONMENTAL CONDITIONS**

Temperature:	Operating:	-4°F to +122°F (-20°C to +50°C)
	Storage:	$-67^{\circ}F$ to $+149^{\circ}F$ ( $-55^{\circ}C$ to $+65^{\circ}C$ )
Humidity:		95% Relative humidity

#### WITHSTAND/CLOSING RATING

10K AIC standard, 22K AIC optional (22K AIC standard on ATS2001D/R)

# **COMPATIBLE BRANCH CIRCUIT BREAKERS**

Siemens®	QAF, QFH, QE, QEH, QFP, QNR, QNRH,
	QP, QF, QPF, QPH, QT, QSAP, HQP
Cutler-Hammer:	BD, BR, BQ, GFC
Square D	НОМ
GE	THQL, THHQL

# **AGENCY APPROVALS**

- cULus67
- Conforms to requirements of NEC/NFPA 70, Article 702.5 and 702.6 for Optional Standby Systems.

# WARRANTY

Covers defects in materials and workmanship for 24 months from date of purchase, subject to inspection. Must be installed by a qualified electrician in accordance with the National Electrical Code and all applicable local codes, with all necessary permits and inspections prior to operation.

For more information, call 1-888-GEN-TRAN or visit www.gen-tran.com.